

TEST REPORT

FLORIDA BUILDING CODE TEST PROTOCOL TAS 100-95

TEST PROCEDURE FOR WIND AND WIND DRIVEN RAIN RESISTANCE OF DISCONTINUOUS ROOF SYSTEMS

April 14, 2004

Client: Nu-Lok USA LLC
711 S. Carson Street, Suite 4
Carson City, NV 89701

Metro-Dade Notification No: PRI04058
Test Date: March 18, 2004
PRI Test No: NLRS-001-02-01

1.1 Description of Discontinuous Roof System:

Prepared Roof Covering

Slate: Natural Vermont Slate
Dimensions: Nominal ¼ inch thick X 9 -16 inches wide X 16 inches long
Manufacturer: Greenstone Slate Company, Poultney, VT

Fastening System: Nu-Lok (Fastening) Roofing System (Drawings in Appendix B)
Manufacturer: Nu-Lok USA LLC

Underlayment

Name: Ice & Water Shield®
Type: Self adhering
Manufacturer: Grace Construction Products

Other Materials

Valley Metal: Galvalume, Field formed Soaker
Dimensions: 20 gauge 9 X 24

Counter Batten: 1 x 2 inch Pressure treated wood

Batten: 18 gauge AZ-55 Galvalume™ steel formed 'Z'
Link Channel: 0.031 inches, AZ-55 Galvalume™
Wire Clip: 0.063 inches in diameter 316 Stainless Steel
Manufacturer: Nu-Lok Roofing Systems

NLRS-001-02-01

PRI Accreditations: IAS-ES TL-189; State of Florida; Metro-Dade 03-0515.04; CRRC

The test results, opinions, or interpretations are based on the material supplied by the client. This report is for the exclusive use of stated client. No reproduction or facsimile in any form can be made without the client's permission. This report shall not be reproduced except in full without the written approval of this laboratory. PRI Asphalt Technologies, Inc. assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

1.9 Volume of water, which infiltrated the sheathing at area of ridge vent.

Not applicable in this test.

1.10 Water Infiltration Through Sheathing.

None


1.11 Shingles Which Blow Off, Tear or Blow Upward Without Reseating:

None


2.0 Result of Testing:

Pass

The sample submitted for testing complies with all the requirements of Florida Build Code Test Protocol TAS 100-95, **TEST PROCEDURE FOR WIND AND WIND DRIVEN RAIN RESISTANCE OF DISCONTINUOUS ROOF SYSTEMS.**

Signed: 
Gary H. Griswold
Manager, Testing Services

Date: 4/9/04

Approved: 
Charles L. Thomas
Professional Engineer
P.E. Number: 29439

Date: 6/29/04

NLRS-001-02-01

PRI Accreditations: IAS-ES TL-189; State of Florida; Metro-Dade 03-0515.04; CRRC

The test results, opinions, or interpretations are based on the material supplied by the client. This report is for the exclusive use of stated client. No reproduction or facsimile in any form can be made without the client's permission. This report shall not be reproduced except in full without the written approval of this laboratory. PRI Asphalt Technologies, Inc. assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.